

# AOS Semiconductor Product Reliability Report

# AO4423/AO4423L, rev A

## **Plastic Encapsulated Device**

## **ALPHA & OMEGA Semiconductor, Inc**

495 Mercury Drive Sunnyvale, CA 94085 U.S.

Tel: (408) 830-9742

www.aosmd.com

Nov 1, 2004



This AOS product reliability report summarizes the qualification result for AO4423. Accelerated environmental tests are performed on a specific sample size, and then followed by electrical test at end point. Review of final electrical test result confirms that AO4423 passes AOS quality and reliability requirements. The released product will be categorized by the process family and be monitored on a quarterly basis for continuously improving the product quality.

## **Table of Contents:**

- I. Product Description
- II. Package and Die information
- III. Environmental Stress Test Summary and Result
- IV. Reliability Evaluation
- V. Quality Assurance Information

### I. Product Description:

The AO4423 uses advanced trench technology to provide excellent R<sub>DS(ON)</sub>, and ultra-low low gate charge with a 25V gate rating. This device is suitable for use as a load switch or in PWM applications. It is ESD protected. AO4423L (Green Product) is offered in a lead-free package.

Absolute Maximum Ratings T <sub>A</sub> =25°C unless otherwise noted						
Parameter		Symbol	Maximum	Units		
Drain-Source Voltage		V <sub>DS</sub>	-30	V		
Gate-Source Voltage		V <sub>GS</sub>	±25	V		
Continuous Drain	T <sub>A</sub> =25°C		-15			
Current <sup>G</sup>	T <sub>A</sub> =70°C	I <sub>D</sub>	-12.1	А		
Pulsed Drain Current <sup>C</sup>		I <sub>DM</sub>	-80			
	T <sub>A</sub> =25°C	PD	3.1	w		
Power Dissipation <sup>B</sup>	T <sub>A</sub> =70°C		2	vv		
Junction and Storage						
Temperature Range		T <sub>J</sub> , T <sub>STG</sub>	-55 to 150	D°		

Thermal Characteristics							
Parameter		Symbol	Тур	Max	Units		
Maximum Junction-to- Ambient	t ≤ 10s		26	40	°C/W		
Maximum Junction-to- Ambient	Steady- State	R <sub>θJA</sub>	50	75	°C/W		
Maximum Junction-to-Lead	Steady- State	R <sub>θJL</sub>	14	24	°C/W		



## II. Die / Package Information:

Process	AO4423 Standard sub-micron low voltage P channel process	AO4423L (Green Compound) Standard sub-micron low voltage P channel process
Package Type	8 leads SOIC	8 leads SOIC
Lead Frame	Copper with Solder Plate	Copper with Solder Plate
Die Attach	Ag epoxy	Ag epoxy
Bond wire	2 mils Au wire	2 mils Au wire
Mold Material	Epoxy resin with silica filler	Epoxy resin with silica filler
Filler % (Spherical/Flake)	50/50	100/0
Flammability Rating	UL-94 V-0	UL-94 V-0
Backside Metallization	Ti / N / Ag	Ti / N / Ag
Moisture Level	Up to Level 1 *	Up to Level 1*

Note \* based on info provided by assembler and mold compound supplier

## III. Result of Reliability Stress for AO4423 (Standard) & AO4423L (Green)

Test Item	Test Condition	Time Point	Lot Attribution	Total Sample size	Number of Failures
Solder Reflow Precondition	Normal: 1hr PCT+3 cycle IR reflow@240 °c (260°c for Green)	0hr	Normal: 48 lots Green: 16 lots	9405 pcs	0
HTGB	Temp = 150 C, Vgs=100% of Vgsmax	168 / 500 hrs 1000 hrs	Normal: 1 lot (note A*)	82 pcs 77+5 pcs / lot	0
HTRB	Temp = 150 C, Vds=80% of Vdsmax	168 / 500 hrs 1000 hrs	Normal: 1 lot (note A*)	82 pcs 77+5 pcs / lot	0
HAST	130 +/- 2 C, 85%, 33.3 psi, Vgs = 80% of Vgs max	100 hrs	Normal: 30 lots Green: 14 lots (note B**)	2420 pcs 50+5 pcs / lot	0
Pressure Pot	121 C, 15+/-1 PSIG, RH=100%	96 hrs	Normal: 48 lots Green: 16 lots (note B**)	3520 pcs 50+5 pcs / lot	0
Temperature Cycle	-65 to 150 deg C, air to air, 0.5hr per cycle	250 / 500 cycles	Normal: 48 lots Green: 15 lots (note B**)	3465 pcs 50+5 pcs / lot	0



III. Result	of Reliability Stress	for AO442	3 (Standard) & A	04423L (Gre	en)
Continues	_			-	-

DPA	Internal Vision	NA	5	5	0
	Cross-section		5	5	
	X-ray		5	5	
CSAM		NA	5	5	0
Bond Integrity	Room Temp	0hr	40	40 wires	0
	150°C bake	250hr	40	40 wires	
	150°C bake	500hr	40	40 wires	
Solderability	230°C	5 sec	15	15 leads	0
Die shear	150°C	Ohr	10	10	0

**Note A:** The HTGB and HTRB reliability data presents total of available AO4423 and AO4423L burn-in data up to the published date.

**Note B:** The pressure pot, temperature cycle and HAST reliability data for **AO4423L** comes from the AOS generic green compound package qualification data.

## **IV. Reliability Evaluation**

### FIT rate (per billion): 42.7 MTBF = 2671 years

500 hrs of HTGB, 150 deg C accelerated stress testing is equivalent to 15 years of lifetime at 55 deg C operating conditions (by applying the Arrhenius equation with an activation energy of 0.7eV and 60% of upper confidence level on the failure rate calculation). AOS reliability group also routinely monitors the product reliability up to 1000 hr at and performs the necessary failure analysis on the units failed for reliability test(s).

The presentation of FIT rate for the individual product reliability is restricted by the actual burn-in sample size of the selected product (AO4423). Failure Rate Determination is based on JEDEC Standard JESD 85. FIT means one failure per billion hours.

**Failure Rate** =  $\text{Chi}^2 \times 10^9 / [2 \text{ (N) (H) (Af)}] = 1.83 \times 10^9 / [2 (164) (500) (258.24)] = 42.7$ **MTBF** =  $10^9 / \text{FIT} = 2.34 \times 10^7 \text{hrs} = 2671 \text{ years}$ 

 $Chi^2$  = Chi Squared Distribution, determined by the number of failures and confidence interval N = Total Number of units from HTRB and HTGB tests

**H** = Duration of HTRB/HTGB testing

**Af** = Acceleration Factor from Test to Use Conditions (Ea = 0.7eV and Tuse = 55C) Acceleration Factor [**Af**] = **Exp** [Ea / **k** (1/Tj u - 1/Tj s)]

#### Acceleration Factor ratio list:

	55 deg C	70 deg C	85 deg C	100 deg C	115 deg C	130 deg C	150 deg C
Af	258	87	32	13	5.64	2.59	1

Tj s = Stressed junction temperature in degree (Kelvin), K = C+273.16

Tj u =The use junction temperature in degree (Kelvin), K = C+273.16

 $\mathbf{k}$  = Boltznan's constant, 8.617164 X 10 E<sup>-5</sup>V / K



## V. Quality Assurance Information

Acceptable Quality Level for outgoing inspection: **0.1%** for electrical and visual. Guaranteed Outgoing Defect Rate: **< 25 ppm** Quality Sample Plan: conform to **Mil-Std-105D** 

#### Contacts:

Wei Liu, Engineer of Failure Analysis and Reliability <u>wliu@aosmd.com</u> Jackey Wang, Engineer of Failure Analysis and Reliability <u>zwang@aosmd.com</u> Fred Chang, Manager of Failure Analysis and Reliability <u>fchang@aosmd.com</u> Wilson Ma, Senior Director of Quality Assurance <u>wma@aosmd.com</u>